BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2018-19/OW/WORK_INDENT34768

APPROVED SCHEDULE - B

STP/BBMP/E-PMT/22/2018-19, Date: 27.02.2019

Construction of RO Plant in ward no 05 Byatarayanapura Sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of D V Kumar ( )	
				In Figures	In Words
1	25.38	KSRB 2-2.1 : Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(a) / 2.3.5 Page No. 5 / Item No. 2.3 of PWD SR 2016-17	Cum	176.56	Rupees One Hundred Seventy Six and Fifty Six Paise Only
2	4.15	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. Page No.12, Item No. 4.3 of PWD SR 2016-17	Cum	4546.75	Rupees Four Thousand Five Hundred Forty Six and Seventy Five Paise Only
3	2.89	KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 Page No. 23 / Item No. 5.6, PWD SR 2016-17	Cum	3911.5	Rupees Three Thousand Nine Hundred Eleven and Fifty Paise Only
4	1.95	KSRB 5.3-3 : Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 Page No. 23 / Item No. 5.9, PWD SR 2016-17	Cum	4675.7	Rupees Four Thousand Six Hundred Seventy Five and Seventy Paise Only
5	25.38	KSRB 2.3 : Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20cms, in depth, compacting each deposited layers by ramming after watering with lead upto 50m, and lift upto 1.5m, including cost of all labour complete as per specifications, specification. No. KBS 2.9, Page No. 6 / Item No. 2.10 / PWD SR 2016-17	Cum	118.6	Rupees One Hundred Eighteen and Sixty Paise Only
6	35.7	KSRB 5-14 : Providing and constructing load bearing wall with solid concrete blocks of size 400x150x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications. KBS No.5.4 Page No. 25 / Item No. 5.26.2, PWD SR 2016-17	Sqm	847.3	Rupees Eight Hundred Forty Seven and Thirty Paise Only
7	9.4	Providing and laying cement concrete using 20 mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete (RMC) M 20 for R.C.C works laid in 15 cms thick layers and well compacted vibrating, curing, for raft foundation column footing , main and secondary beams with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Page No. 18, Item No. 4.48, PWD SR 2016-17	Cum	5492.1	Rupees Five Thousand Four Hundred Ninety Two and Ten Paise Only
8	0.67	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 - TMT bars Fe 500 Page No. 17 / Item No. 4.46.2, PWD SR 2016-17	Tonne	56619.0	Rupees Fifty Six Thousand Six Hundred Nineteen Only

20/03

	pproved Qty.	Description	Unit	Approved Tender Rates of D V Kumar ( )	
				In Figures	In Words
9	65.79	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth cills and string courses cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 Page No. 15 / Item No. 4.31 PWD SR 2016-17	Sqm	273.72	Rupees Two Hundred Seventy Three and Seventy Two Paise Only
10	18.81	KSRB15-3-13 : Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to ceiling including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. Page No. 114, Item No. 15.21 of PWD SR 2016-17	Sqm	180.3	Rupees One Hundred Eighty and Thirty Paise Only
11	37.23	KSRB15-3.12 :Providing 20mm thick cement plaster in single coat with cement mortar 1:6, to stone masonry & concrete surface including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. Page No. 114, Item No. 15.21 of PWD SR 2016-17 (Inside Plastering)	Sqm	194.3	Rupees One Hundred Ninety Four and Thirty Paise Only
12	56.04	KSRB15-7 : Providing lime rendering for plastering to wall and ceiling, including cost of materials, labour, curing complete as per specifications. Page No. 115, Item No. 15.33, PWD SR 2016-17	Sqm	23.36	Rupees Twenty Three and Thirty Six Paise Only
13	42.03	KSRB15-3.9 :Providing 18mm thick cement plaster in single coat with cement mortar 1:6, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. Page No. 114 / Item No. 15.17, PWD SR 2016-17 (Outside Wall)	Sqm	183.0	Rupees One Hundred Eighty Three Only
14	93.27	KSRB 15-14.1 : Providing and applying two coats with oil bound washable distemper of approved brand and shade on wall surface including priming coat with distemper primer after throughly brooming the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications. Page No. 117 / Item No. 15.49.1, PWD SR 2016-17	Sqm	66.3	Rupees Sixty Six and Thirty Paise Only
15	42.03	KSRB 15-16.1 : Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications. - with primer. Page No. 117 / Item No. 15.53.2, SR 2016-17.	Sqm	78.5	Rupees Seventy Eight and Fifty Paise Only
16	29.43	KSRB 15-18.2 : Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications. (Page No. 120 Item No. 15.74 of SR 2016-17).	Sqm	76.6	Rupees Seventy Six and Sixty Paise Only
17	12.41	Providing and fixing Special make glazed Vitrified tiles (Granomite finish) of approved make, quality and colour of size 600x600x10mm thick fixed on existing flooring with a special roffe adhesive for flooring and skirting etc., complete including providing spears at required interval and removing stains etc., complete. (P.No. 107, I.No. 14.43 of SR 2016-17).	Sqm	1111.7	Rupees One Thousand One Hundred Eleven and Seventy Paise Only
18	4.8	Providing and laying/fixing cement base, precast, pre polished cement concrete, designer tiles 25mm thick for flooring conforming to IS 1237 heavy duty tiles for flooring, treads of steps and landing, laid on a bed of 12mm thick cement mortar 1:3 mis finished with flush pointing using white cement, including cost of materials, including cutting, griding the edge to half/full round wherever required, labour, curing complete as per specification. P.No. 109, I.No. 14.62 of PWD SR 2016-17	Sqm	1013.6	Rupees One Thousand Thirteen and Sixty Paise Only

20/05

	pproved Qty.	Description	Unit	Approved Tender Rates of D V Kumar ( )	
				In Figures	In Words
19	1.08	KSRB 7.7 : Providing and fixing in position in cement concrete 1:3:6 steel glazed windows and ventilators side hung/top hung fully openable as per approved drawings using Z angles of 25x33x3mm, weighing 1.419 Kg/m both for outer and inner frames and central mullion section of size 25x46x3mm. weighing 2.28Kg/m duly providing T section 19x19x3mm weighing 0.839 kg/m for glazing of windows not more than 34 cms. c to c including providing and fixing 4mm. thick reeded glass with teakwood beading of required size, all steel sections should confirm to I.S 7452:1990, 4nos. of holdfasts of approved size, section should be cut to length welded and electrically grinded subdividing frames of unit shall be tenonned and revetted into the frames electrically. All the steel surface shall be throughly cleaned free of rust and painted with one coat of anti-corosive paint and finishing with two coats of ready mix paint of approved colour and make including cost of materials, fixtures, labour and HOM of machinery complete as per specifications. Specification No. KBS 7.12.1 / 7.12.2 / 7.12.3 / 7.12 Page No. 31, Item No. 707 PWD SR 2016-17	Sqm	3297.7	Rupees Three Thousand Two Hundred Ninety Seven and Seventy Paise Only
20	6.3	KSRB 7.5 : Providing and fixing pull and push type rolling shutters of approved make out of 18 guage, 75mm wide cold rolled steel laths of convex corrugation, with side guides and bottom rail, with interlocking arrangements for steel laths by means of alternate clips, suspension shaft with High tension coil type springs two numbers, mounted on specially designed pipe shaft, with bracket plates, guide channels, ball bearing arrangements, for inside & outside locking with push & pull operations complete including pulling hooks, 4Nos. handles with all fittings and accessories, painted with a coat of red lead paint (without top cover) cost of materials, labour, HOM of machinery complete as per specifications. Shutter size 3mx2.8 m. Specification No. KBS 7.10 / 7.12. (P.No. 31, I.No. 7.5 of CSR 2016-17)	Sqm	2673.7	Rupees Two Thousand Six Hundred Seventy Three and Seventy Paise Only
21	6.3	KSRB 7.15 : Providing, fabricating, assembling and fixing in position aluminium partitions using aluminium sections of mat finish or glassy finish in combination of plain grove, single grove and double grove as per requirements for the frames of overall size 63.5mm x 38.1mm. with thickness of 2mm. having section weight, plain sections 1.054kg/m, single grove thickness 1.95mm. section weight 1.094kg/m, double grove thickness 1.9mm section weight 1.094kg/m and bottom member 114.3 mm. x 44.45mm. thickness 3.18mm. weight 2.646 kg/m; aluminium louvres section of size 36.5mmx34.93mm 1.45mm. thick section weight 0.429kg/m; bottom portions provided with 12mm. thick prelaminated sheet both sides of approved colour lamination exterior grade upto 0.9m height, spacing of vertical member not exceeding 0.6 m. c to c; sections are cut to the required lengths, joints mitered and corners grinded subdividing frames tennoned and rivetted to the frames; the assembled frame stiffened with corner angles, stripped and fixed with screws, rawl plugs and teak wood gutties to R.C.C.columns on sides, R.C.C. lintels or beams at top and floor at bottom, including cutting chistelling and making good with cement mortar to match the surface; providing and fixing 5.5mm. thick plain glass for middle portion viz., 0.9m. to 2.13 m. and top panel with louvres sections; the glass and panels fitted withglazing clips of 19mmx17.3mm. of thickness 0.9mm. weight 0.124kg/ m, aluminium sections treated for removal of any rust and prevention of further rust formation, coated with greasy materials for non-adherence of mortars or any other sticky materials; vertical members embedded in the flooring by making suitable sized holes and fixing with cement mortar, with necessary opening for fixing of door of standard size (excluding cost of door) all the frame throughly cleaned, free from rust, scale or dirt including cost of materials, fixtures, labour and HOM of machinery complete as per specifications. using aluminium section anodized to 12 - 15 microns. Page No. 35, Item No. 7.15.1 PWD SR 2016-17	Sqm	3021.2	Rupees Three Thousand Twenty One and Twenty Paise Only

20/05

		Description	Unit	Approved Tender Rates of D V Kumar ( )	
				In Figures	In Words
	5.4	Earthwork excavation for pipeline trenches including deporiting or bank up to a lead of 50 mtrs including sharing and strutting danger lighting and using site rails and boming poles at every 100 mtrs wherever necessary as directed in th following strructure manhole. Page No. 01/ Item No.1.2.2 / PRED SR 2012-13 Hard Soil	Cum	162.6	Rupees One Hundred Sixty Two and Sixty Paise Only
3	20	Providing and instalation at site of works P.V.C.Pipes including cost of pipes and specials and incluidng lowring into trenches, laying true to line, level and perfect linking at joints, leak proof including jointing encasing the pipe alround to a depth Not less than 15cm with grave or selected earth avalabile from the execavation Etc., Page No.15 item No.3.4.2 b PRED SR 2012-13.	Rmtr	135.8	Rupees One Hundred Thirty Five and Eighty Paise Only
24	1.8	KSRRB M1200-46. Sand filling in wells complete as per drawing and technical specifications MORTH Specification No.1207 Page No. 213, Page No. 26.124, PWD SR 2016-17	Cum	2527.9	Rupees Two Thousand Five Hundred Twenty Seven and Ninety Paise Only
25	3.6	Refilling the basement and pipeline treanches with secleted available earthe for trench excavation including authority condition in layers from thedi including disponsary of the sunplus earth with a heavy 200 mtrs Page No. 3 / Item No. 1.6 / PRED SR 2012-13	Cum	52.75	Rupees Fifty Two and Seventy Five Paise Only
26	2	KSRB13-6.3-7 : Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 65mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No.KBS 13.2.6 / 13.3. P. No.92 / I. No. 13.38 PWD SR 2016-17	Each	2361.0	Rupees Two Thousand Three Hundred Sixty One Only
27	1	10000 LPD R.O. Plant RAW WATER PUMP:Quantity : 1No. Type: Centrifugal Mono Block MOC & Make : UKL Motor Rating : 0.75 HP,PRESSURE SAND FILTER:,Quantity : 1No.Capacity : 1000 LPH MOC & Make of Housing : UKL,MOC & Make of Cartridge : UKL,Capcity : 100 LPH,MOC & Make of Vessel : UKL,Diameter : 40 mm,Type of Valve : Single Multiport,media : Support bed + Sand,MICRON CARTRIDGE FILTER :,Quantity : 1 Set.,Filter Rating : 5 Microns,Size : 20 " Long,ANTISCALANT DOSING PUMPS:,Quanity : 1 Set,Type : Electro - magnetic,Capacity : 1.5 LPH @ 4 Bar,HIGH PRESSURE PUMP:,Quantity : 1 No,Capacity : 1700 LPH,Type of Pump : Vertical Multistage Centrigugal Pump,MOC : SS 304,Motor Rating : 2 HP, 3 Phase,Maximum Pressure : 12 Kg/ cm2,Make : UKL ,RESERVE OSMOSIS SYSTEM :Quantity : 1 No,Capacity : 1000 LPH ,Module Type,Membrane Specifications {Polyamde},Make of Membrane : UKL,UV STERILISER,Max. Treatment Flow : 1 m3/hr,No. of Lamps : 1 No,Wattage : 39 W,Efficiency : 99.99%,Material of Construction : SS 304,PRODUCT WATER QUALITY:,Appearance : Crystal Clear,Abide by the ISO Standards,S S Tank : 304 Grade with 16 guage 2000 liters Capacity,304 Grade 10 Gauage SS Pipe {with stream valve} 25 Ft,COIN BOOTH DISPENSING UNIT,for 5 Liters & 20 Ltrs Separately,Raw Water Stoage Tank : Dunction - for Storage of Raw Water,Type / MOC : Two / Three Layered PE tanks White / Transparent in color made from virgin material of food grade Quality suitabke fir the purpose of providing,Storage Drinking / Portable Water : 5000 Liters Capacity	Nos	815926.0	Rupees Eight Hundred Fifteen Thousand Nine Hundred Twenty Six Only
28	6	ELECTRIFICATION Supplying and wiring adopting loop system in existing PVC Conduit / casing capping using 1100V grade, COPPER conductor flexible multistrand FRLS PVC insulated, 2 X1.5Sq.mm Cable confirming to the GTP, with a 6Amps flush type SP control switch shall be fixed on the existing plastic sheet / gang box, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block. complete for each outlet. GROUP A b) Medium point above 3Mtr upto 6Mtr from tapping point to out let via switch etc., complete and as per the directions of the Engineer-in-charge of the work	Point	212.0	Rupees Two Hundred Twelve Only
29	6	c) Long point above 6Mtr upto 10Mtr from tapping point to out let via switch	Point	314.0	Rupees Three Hundred Fourteen Only
30	30	Supplying and flush mounting teak wooden box without front plank, made of not less than 12mm thick wood, after due groove cutting, Finishing with necessary cement plastering complete (1.6.5) 4"x4"x3" (101x101x76mm) etc., complete and as per the directions of the Engineer-in-charge of the work	Each	59.0	Rupees Fifty Nine Only

2016

		Description	Unit	Approved Tender Rates of D V Kumar ( )	
				In Figures	In Words
	18	(1.6.1) 12"x12"x3" (300x300x76mm)	Each	100.0	Rupees One Hundred Only
	15	(1.6.3)10"x7"x3" (254x178x76mm)	Each	75.25	Rupees Seventy Five and Twenty Five Paise Only
33	33333	Supplying 4mm thick plastic sheet with necessary nitches for fixing switches, regulators etc., and fixing on existing wooden or metal box using N.F. screws etc., complete and as per the directions of the Engineer-in-charge of the work	SqCM	0.22	and Twenty Two Paise Only
34	20	Extra for Groove cutting in brick wall/CC floor to the suitable depth for concealing of Conduit/GI pipe and plastering, finishing upto wall surface complete. upto 50mm conduit in brick wall etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	18.1	Rupees Eighteen and Ten Paise Only
35	20	Supplying heavy gauge PVC Conduit Pipe 19/20 mm dia 2 mm thick with suitable size bends, metal junction boxes adhesive paste etc., by groove cutting in the wall and fixing by bracing U or J hooks and cement plastering up to the wall surface and run with 18 SWG GI fish wire run throughout the conduit wherever necessary etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	48.5	Rupees Forty Eight and Fifty Paise Only
36	4	Supplying and fixing PBBC/Bakelite straight or slant batten holder and wiring with 60w/230 volts lamps etc., complete and as per the directions of the Engineer-in-charge of the work	Each	76.1	Rupees Seventy Six and Ten Paise Only
37	4	Supplying patti type fluorescent tube light fitting of 2' - suitable for 14 watts fluorescent tube fitting, made out of M.S. Sheet and stove enameled with HF Electronic Ballast , locking type brass contact holders mounted on double fold type sheet base fully wired for use on 230 volts AC . Supply including T5 lamp etc., complete and as per the directions of the Engineer-in-charge of the work	Each	511.0	Rupees Five Hundred Eleven Only
38	15	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand Copper with low conductor resistance single core wire in open or concealed system of wiring with specified IS-694:1990 & confirming to GTP of GROUP -A 1.5 sqmm etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	16.0	Rupees Sixteen Only
39	8	Supplying and fixing cast Aluminum round or oblong type bulk head fitting with GI wire guard, glass cover with 60/100 watts 230V GLS lamp etc., complete and as per the directions of the Engineer-in-charge of the work	Each	646.0	Rupees Six Hundred Forty Six Only
40	1	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipment's on the meter board using 40mm dia 2.90mm thick GI pipe 2.5 mtr long buried in a pit ... The pit should be filled with equal proportion of salt and charcoal 150mm all-round the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size as per ISI specification 7.3.3. of IS 732 using 12mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 through holes of 122 mm dia etc., complete and as per the directions of the Engineer-in-charge of the work	No	2359.0	Rupees Two Thousand Three Hundred Fifty Nine Only
41	25	Supplying of 1.1 KV LT UG cable having aluminum conductor PVC insulated, extruded inner sheathed, galvanized, steel strip (except 2CX10Sq.mm wire armoured) confirming to IS-3975:1990 (No. of Strip indicated in GTP) & extruded PVC outer sheathed armoured cable with specified IS-1554 Part-1:1988 & confirming to GTP of GROUP-A etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	121.45	Rupees One Hundred Twenty One and Forty Five Paise Only
42	25	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required.In existing trench/duct etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	8.3	Rupees Eight and Thirty Paise Only
43	20	Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete For Cutting Road Surface etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	73.5	Rupees Seventy Three and Fifty Paise Only

20/05

	pproved Qty.	Description	Unit	Approved Tender Rates of D V Kumar ( )	
				In Figures	In Words
44	4	Supplying and fixing of class A (medium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV 40mm dia GI pipe etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	298.0	Rupees Two Hundred Ninety Eight Only
45	1	Supplying and fixing L.T. cast Iron pot heads suitable for 1.1 KV class UG cable filled with necessary bitumen/insulating compound complete with terminals, clamps, bolts, nuts and washers 16Sqmm etc etc., complete and as per the directions of the Engineer-in-charge of the work	No.	242.0	Rupees Two Hundred Forty Two Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

20/05

20/05